Tennessee Code Annotated Section 68-221-711 and Consolidated Utility District Policy

INSTALLATION, ROUTINE INSPECTIONS AND TESTING OF DEVICES

- To assure that ALL devices are working properly, devices must be tested every 365 days by a tester with a Certificate of Competency and approved by Consolidated Utility District (CUD).
- All lawn irrigation systems must be tested during startup period. Testing prior to shut down (winterization) WILL NOT BE ACCEPTABLE.
- Any time a device has been partially disassembled for cleaning, repair, or replaced with a new device, that device must be tested. A copy of the test must be submitted to CUD.
- Upon completion of ANY TEST (passed or failed), a copy of the test report must be submitted to CUD by the certified tester.
- All devices must be tested immediately following installation.
- All backflows must be installed outside, above ground, according to TDEC regulations and CUD policy. A permit MUST be pulled at CUD's office.

ALLOWED TIME TO REPAIR A FAILED DEVICE

ALL FAILED DEVICES must be repaired, restested, and passed WITHIN 30 DAYS of the original test.

INSTALLING CORRECT BACKFLOW DEVICE

- All commercial, irrigation, apartments, churches, public pools, and all other hazards are required to carry a REDUCE PRESSURE ZONE DEVICE, according to TDEC. DOUBLE CHECK DEVICES are allowed only on Classes 1-3 fire systems.
- In the case of a violation, water service will be discontinued, and the customer will be assessed a $500 fine for failure to comply with regulations.
- If you have any questions, please call CUD Water Quality Coordinator Randy Harrell at (615) 225-3326 or email rharrell@cudrc.com.

CONSOLIDATED UTILITY DISTRICT
Rutherford County, Tennessee