FIRE LINES

All Fire Lines connected to Consolidated Utility District of Rutherford County's (CUDRC) public water mains shall be metered. It will be the developer/contractor's responsibility to furnish and install the meter as specified by CUDRC. The connection shall be subject to a monthly demand fee plus any water used on a monthly basis. Installation and materials shall be as follows:

- A Meter Application shall be completed and submitted for review by CUDRC during the planning phase to ensure proper meter sizing.
- Shop Drawing submittals shall be made to CUDRC's Meter Department for review and approval.
- A design drawing shall be submitted to CUDRC for review and approval prior to start of any construction.
- The developer/contractor shall provide and install the materials for the tap to the main line. CUDRC will make the tap to the existing main line up to twenty four inches (24") in diameter, subject to current tapping fees set forth by CUDRC.
- Installation shall be completed as specified by CUDRC and inspected by an authorized official of CUDRC.
- All fire line installations shall require a double check valve backflow preventer installed at the exterior of the structure and enclosed in an above ground hot-box as specified in CUDRC's cross-connection policy.
- All new construction, renovations, remodels, additions, and the like must comply with metering the fire line. Renovations, remodels, and additions with existing fire lines must be retrofitted with installing a fire meter, vault, and double check valve style backflow preventer at the cost to the developer per CUD requirements.